BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, (Project) Rajarajeshwari Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: BBMP/EE/Proj/RRN/TEN/01/2019-20, Date: 25.04.2019

Indet No: BBMP/2019-20/BD/WORK_INDENT35373

SCHEDULE -B

Name of Work:-CONSTRUCTION OF MPED BUILDING (GOVT SCHOOL) AT JALAHALLI VILLAGE IN WARD NO.16

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Clearing grubbing road lane including up rooting rank vegitation , grass , brush , shrubs , sapling & trees of girth up to 300mm by manual means, in area of light jungle , removal of stumps , disposal of un serviceabale materials , stacking of serviceabale materials with in a lead of 100 mtr from road boundary , labour charges complete as per specifications	Sqm	1600.00	7.00	Rupees Seven Only
2	Dismanteling of Exsisting structures like Culverts, Bridges, retaining wall & other structures compraising of masanry, cement concrete, wood work, steel work including T& P and scaffolding wherever necessary, sorting the Dismentalled metrial,disposoble of unserviceble material & stacking servicable material with lead of 1000 mts, complete as per specification 1.) Lime concrete/ Cement Concrete -KSRRB M200- 13.1 - do- II by mechanicaal means A cement Concrete Grade M 15-M20	Cum	81.00	428.00	Rupees Four Hundred Twenty Eight Only
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.KSRRB M200-14.2. –do– Dismantling brick/Tile work B. In cement mortar. MORTH Specification No. 202	Cum	13.57	303.00	Rupees Three Hundred Three Only
4	Dismanteling of Exsisting structures like Culverts, Bridges, retaining wall & other structures compraising of masanry, cement concrete, wood work, steel work including T& P and scaffolding wherever necessary, sorting the Dismentalled metrial,disposoble of unserviceble material & stacking servicable material with lead of 1000 mts, B13 complete as per specification !!!) Dismanteling of Stone masonary MORTH Specification 202	Cum	105.00	303.00	Rupees Three Hundred Three Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
5	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in IN ORDINARY SOIL not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	1209.59	235.00	Rupees Two Hundred Thirty Five Only
6	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in IN HARD SOIL not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	298.20	351.00	Rupees Three Hundred Fifty One Only
7	KSRB 2-2.3 : Excavation by manual means for foundation of buildings, water supply & sanitary lines and electrical conduits etc., either in pits or in trenches 1.50m and above in width, in soft rock not exceeding 1.50mtrs in depth including stacking the excavated stuff clear from edges of excavation with lead upto 50mt including cost of explosives, labour, HOM of equipment complete as per specifications.	Cum	131.30	628.00	Rupees Six Hundred Twenty Eight Only
8	Earth work for lowering & levelling the ground other than foundation works by Mechanical means upto 3.0 mt depth including providing shoring stutting and bracing , removal of stumps and other and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required and utilising /transporting the remaining earth upto 1.00km lead. including cost of labour, materials and HOM of machineries etc., complete.	Cum	45.50	84.00	Rupees Eighty Four Only
9	KSRB 3.2: Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor,along the external perimeter of building,expansion joints,over the top surface of consolidated earth on which apron is to be laid,surrounding of pipes and conduits with chloropyriphos emulsifiable concentrates of 20% concentration,including cost of chemical,diluting in water to one percent concentration, labour, HOM of equipments, complete as per specifications.	Sqmt	710.00	128.00	Rupees One Hundred Twenty Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
10	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305	Cum	387.50	375.00	Rupees Three Hundred Seventy Five Only
11	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm & down size graded grinite metel coarse aggregates @ 0.892 cum & fine aggregates @ 0.465 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms, thick well compacted, in foundation & plinth, cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	266.10	6264.00	Rupees Six Thousand Two Hundred Sixty Four Only
12	Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 240kgs, with 20mm & down size graded grinite metel coarse aggregates @ 0.69 cum & fine aggregates @ 0.459 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms, thick well compacted, in foundation & plinth & Cills including cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	63.10	6755.00	Rupees Six Thousand Seven Hundred Fifty Five Only
13	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Ground Floor	Cum	238.30	7723.00	Rupees Seven Thousand Seven Hundred Twenty Three Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
14	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exeeceding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - First Floor	Cum	36.77	7785.00	Rupees Seven Thousand Seven Hundred Eighty Five Only
15	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exeeceding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Second Floor	Cum	5.90	7847.00	Rupees Seven Thousand Eight Hundred Forty Seven Only
16	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exeeceding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Third Floor	Cum	5.90	7909.00	Rupees Seven Thousand Nine Hundred Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
17	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Ground Floor	Cum	260.43	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
18	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - First Floor	Cum	114.46	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
19	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Second Floor	Cum	114.46	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
20	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Third Floor	Cum	123.46	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
21	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Terrace Floor	Cum	9.98	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
22	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for Foundation , footing , bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	478.40	287.00	Rupees Two Hundred Eighty Seven Only
23	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Ground Floor	Sqm	1082.00	318.00	Rupees Three Hundred Eighteen Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
24	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - First Floor	Sqm	467.00	324.00	Rupees Three Hundred Twenty Four Only
25	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Second Floor	Sqm	344.50	330.00	Rupees Three Hundred Thirty Only
26	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Third Floor	Sqm	344.50	336.00	Rupees Three Hundred Thirty Six Only
27	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Terrace Floor	Sqm	24.90	343.00	Rupees Three Hundred Forty Three Only
28	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Ground Floor	Sqm	394.80	454.00	Rupees Four Hundred Fifty Four Only
29	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - First Floor	Sqm	238.60	461.00	Rupees Four Hundred Sixty One Only
30	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Second floor	Sqm	174.80	467.00	Rupees Four Hundred Sixty Seven Only
31	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Second floor	Sqm	174.80	473.00	Rupees Four Hundred Seventy Three Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
32	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Terrace floor	Sqm	30.40	479.00	Rupees Four Hundred Seventy Nine Only
33	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Ground Floor	Sqm	592.10	683.00	Rupees Six Hundred Eighty Three Only
34	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - First Floor	Sqm	567.70	683.00	Rupees Six Hundred Eighty Three Only
35	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Second Floor	Sqm	452.70	683.00	Rupees Six Hundred Eighty Three Only
36	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Third Floor	Sqm	535.00	683.00	Rupees Six Hundred Eighty Three Only
37	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Terrace Floor	Sqm	34.70	683.00	Rupees Six Hundred Eighty Three Only
38	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Ground Floor	Sqm	45.30	842.00	Rupees Eight Hundred Forty Two Only
39	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - First Floor	Sqm	29.90	848.00	Rupees Eight Hundred Forty Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
40	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Second Floor	Sqm	23.10	854.00	Rupees Eight Hundred Fifty Four Only
41	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Third Floor	Sqm	23.10	860.00	Rupees Eight Hundred Sixty Only
42	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Terrace Floor	Sqm	2.70	867.00	Rupees Eight Hundred Sixty Seven Only
43	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Ground Floor	Sqm	28.50	590.00	Rupees Five Hundred Ninety Only
44	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. First Floor	Sqm	28.50	596.00	Rupees Five Hundred Ninety Six Only
45	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Second Floor	Sqm	22.80	602.00	Rupees Six Hundred Two Only
46	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Third Floor	Sqm	22.80	608.00	Rupees Six Hundred Eight Only
47	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Ground Floor	Sqm	36.60	566.00	Rupees Five Hundred Sixty Six Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
48	Providing and laying in position reinforced cement coenrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. First Floor	Sqm	37.70	572.00	Rupees Five Hundred Seventy Two Only
49	Providing and laying in position reinforced cement coenrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Second Floor	Sqm	15.70	579.00	Rupees Five Hundred Seventy Nine Only
50	Providing and laying in position reinforced cement coenrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Third Floor	Sqm	15.70	585.00	Rupees Five Hundred Eighty Five Only
51	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Ground Floor	Sqm	37.00	335.00	Rupees Three Hundred Thirty Five Only
52	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. First Floor	Sqm	38.00	341.00	Rupees Three Hundred Forty One Only
53	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Second Floor	Sqm	16.00	348.00	Rupees Three Hundred Forty Eight Only
54	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Third Floor	Sqm	16.00	354.00	Rupees Three Hundred Fifty Four Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
55	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Ground Floor	Rmtr	170.00	25.00	Rupees Twenty Five Only
56	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - First Floor	Rmtr	47.00	25.00	Rupees Twenty Five Only
57	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Second Floor	Rmtr	47.00	25.00	Rupees Twenty Five Only
58	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Third Floor	Rmtr	47.00	25.00	Rupees Twenty Five Only
59	Providing lath plastering cement mortor 1:3, 5 Cm thick with 6 mm dia mild steel @ 20 cm c/c both hiorizantaly & Vertically fixing Chicken Mesh for drop chejja , facia, Backing to cupboard including cost of all materials, labour, providing & removing form work H O M of Machinery , curing, complete as per specifications.	Sqm	158.00	1200.00	Rupees One Thousand Two Hundred Only
60	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Ground Floor	MT	50.00	75241.00	Rupees Seventy Five Thousand Two Hundred Forty One Only
61	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - First Floor	MT	22.00	75827.00	Rupees Seventy Five Thousand Eight Hundred Twenty Seven Only
62	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Second floor	MT	17.80	76413.00	Rupees Seventy Six Thousand Four Hundred Thirteen Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
63	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Third Floor	MT	17.80	76999.00	Rupees Seventy Six Thousand Nine Hundred Ninety Nine Only
64	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Terrace Floor	MT	1.50	77585.00	Rupees Seventy Seven Thousand Five Hundred Eighty Five Only
65	KSRB-5.2-2: Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	161.40	6516.00	Rupees Six Thousand Five Hundred Sixteen Only
66	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. -Ground Floor	Cum	103.90	8425.00	Rupees Eight Thousand Four Hundred Twenty Five Only
67	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - First Floor	Cum	77.20	8487.00	Rupees Eight Thousand Four Hundred Eighty Seven Only
68	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Second Floor	Cum	77.20	8549.00	Rupees Eight Thousand Five Hundred Forty Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
69	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Third Floor	Cum	77.20	8611.00	Rupees Eight Thousand Six Hundred Eleven Only
70	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - Terrace Floor	Cum	41.60	8673.00	Rupees Eight Thousand Six Hundred Seventy Three Only
71	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Ground Floor	Sqm	120.30	1158.00	Rupees One Thousand One Hundred Fifty Eight Only
72	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - First Floor	Sqm	79.80	1164.00	Rupees One Thousand One Hundred Sixty Four Only
73	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Second Floor	Sqm	79.80	1171.00	Rupees One Thousand One Hundred Seventy One Only
74	Construction of partition wall 11.2 cms thick with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with cement mortar 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - Third Floor	Sqm	79.80	1177.00	Rupees One Thousand One Hundred Seventy Seven Only

Signature of the contractor

Signature of the contractor

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
75	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm - Ground Floor	Sqm	356.40	1163.00	Rupees One Thousand One Hundred Sixty Three Only
76	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm -First Floor	Sqm	98.90	1200.00	Rupees One Thousand Two Hundred Only
77	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm -Second Floor	Sqm	45.00	1238.00	Rupees One Thousand Two Hundred Thirty Eight Only
78	Construction of partition wall 10cm thick with table moulded modular burnt bricks of class designation 5.0netwon per sqmm with cemet mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped gelvanisediron of nominal thickness 0.35mm.100mm.labour charges' scaffolding' curing complete as per specification - Ground Floor	Sqm	105.10	978.00	Rupees Nine Hundred Seventy Eight Only
79	Construction of partition wall 10cm thick with table moulded modular burnt bricks of class designation 5.0netwon per sqmm with cemet mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped gelvanisediron of nominal thickness 0.35mm.100mm.labour charges' scaffolding' curing complete as per specification - First Floor	Sqm	104.90	984.00	Rupees Nine Hundred Eighty Four Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
80	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Ground Floor	Sqm	1161.38	303.00	Rupees Three Hundred Three Only
81	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - First Floor	Sqm	417.30	303.00	Rupees Three Hundred Three Only
82	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Second Floor	Sqm	384.80	303.00	Rupees Three Hundred Three Only
83	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Third Floor	Sqm	276.80	303.00	Rupees Three Hundred Three Only
84	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.External Plastering - Terrace Floor	Sqm	242.00	303.00	Rupees Three Hundred Three Only
85	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Ground Floor	Sqm	1475.22	278.00	Rupees Two Hundred Seventy Eight Only
86	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - First Floor	Sqm	910.00	284.00	Rupees Two Hundred Eighty Four Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
87	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Second Floor	Sqm	605.00	291.00	Rupees Two Hundred Ninety One Only
88	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Third Floor	Sqm	605.00	297.00	Rupees Two Hundred Ninety Seven Only
89	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Terrace Floor	Sqm	79.00	297.00	Rupees Two Hundred Ninety Seven Only
90	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Ground floor	Sqm	932.20	263.00	Rupees Two Hundred Sixty Three Only
91	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First floor	Sqm	640.00	269.00	Rupees Two Hundred Sixty Nine Only
92	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second floor	Sqm	548.00	276.00	Rupees Two Hundred Seventy Six Only
93	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third floor	Sqm	548.00	282.00	Rupees Two Hundred Eighty Two Only
94	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Terrace floor	Sqm	23.64	288.00	Rupees Two Hundred Eighty Eight Only

nature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
87	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Second Floor	Sqm	605.00	291.00	Rupees Two Hundred Ninety One Only
88	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Third Floor	Sqm	605.00	297.00	Rupees Two Hundred Ninety Seven Only
89	Providing 15mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal) - Terrace Floor	Sqm	79.00	297.00	Rupees Two Hundred Ninety Seven Only
90	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Ground floor	Sqm	932.20	263.00	Rupees Two Hundred Sixty Three Only
91	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First floor	Sqm	640.00	269.00	Rupees Two Hundred Sixty Nine Only
92	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second floor	Sqm	548.00	276.00	Rupees Two Hundred Seventy Six Only
93	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third floor	Sqm	548.00	282.00	Rupees Two Hundred Eighty Two Only
94	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Terrace floor	Sqm	23.64	288.00	Rupees Two Hundred Eighty Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
95	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Ground Floor	Sqm	201.00	195.00	Rupees One Hundred Ninety Five Only
96	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First Floor	Sqm	91.00	201.00	Rupees Two Hundred One Only
97	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second Floor	Sqm	91.00	207.00	Rupees Two Hundred Seven Only
98	Providing rough cement plastering 15 mm thick in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third Floor	Sqm	91.00	214.00	Rupees Two Hundred Fourteen Only
99	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- First Floor	Sqm	28.00	328.00	Rupees Three Hundred Twenty Eight Only
100	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- Second Floor	Sqm	28.00	334.00	Rupees Three Hundred Thirty Four Only
101	Providing 20mm thick cement plaster in single coat with cement mortor 1:3, to Stone masonary & concrete Surface including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.- Third Floor	Sqm	28.00	340.00	Rupees Three Hundred Forty Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	2	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1		3	4	5	6
102	KSRB 15.8.2 Providing and fixing plaster mesh 150mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	350.00	45.00	Rupees Forty Five Only
103	KSRB 15.8.2 Providing and fixing plaster mesh 200mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	380.00	53.00	Rupees Fifty Three Only
104	KSRB 15.9 Providing and fixing Corner beads 45x45mm size manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along exposed corners of walls, coloumns, lintels including cost of materials, labour for fixing complete . (length of mesh be measured for payment)	Rmtr	49.00	32.00	Rupees Thirty Two Only
105	Providing & applying Two coats of wall putty to inside plasterd walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of materials , cost of labour and scafolding etc complete as per specifications - For All Floors	Sqm	6221.20	70.00	Rupees Seventy Only
106	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Ground Floor	Sqm	1634.00	112.00	Rupees One Hundred Twelve Only
107	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - First Floor	Sqm	605.00	112.00	Rupees One Hundred Twelve Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
108	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Second Floor	Sqm	605.00	112.00	Rupees One Hundred Twelve Only
109	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Third Floor	Sqm	605.00	112.00	Rupees One Hundred Twelve Only
110	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer - Terrace Floor	Sqm	79.00	112.00	Rupees One Hundred Twelve Only
111	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications.-Ground Floor	Sqm	1637.00	117.00	Rupees One Hundred Seventeen Only
112	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -First Floor	Sqm	548.00	117.00	Rupees One Hundred Seventeen Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
3	2	3	4	5	6
	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications.-Second Floor	Sqm	548.00	117.00	Rupees One Hundred Seventeen Only
114	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -Third Floor	Sqm	548.00	117.00	Rupees One Hundred Seventeen Only
115	Providing & applying Painting in in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications. -Terrace Floor	Sqm	24.00	117.00	Rupees One Hundred Seventeen Only
116	Providing Textured paint of approved quality, colour and shade to wall surface after cleaning and rubbing the wall surface with wire brush of medium size emery stone to remove all the loosely adhering particles, the surface is then cleaned with water and ensured that it is in line and level. The textured material is then mixed with 40-50% of clean water until a homogeneous thick slurry is formed, the slurry is left for 5-10 min, to react completely with ingredients. The textured finish prepared as above is then applied to the wall surface with suitable roller/spray gun/putty/ blade / trowel to get the desired finish. The finished surface shall be applied with two coats of exterior paint of approved shade. The rate includes providing and removing scaffolding, all lead and lift and all other incidental charges etc., complete as per directions of the Engineer-in-charge of the work.	Sqm	350.00	439.00	Rupees Four Hundred Thirty Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
117	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Ground Floor	Sqm	1164.00	191.00	Rupees One Hundred Ninety Only
118	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - First Floor	Sqm	417.80	195.00	Rupees One Hundred Ninety Five Only
119	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Second Floor	Sqm	385.00	199.00	Rupees One Hundred Ninety Nine Only
120	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Third Floor	Sqm	277.00	202.00	Rupees Two Hundred Two Only
121	Providing & finishing external walls in two coats over one coat of 100 % acrylic silcon glazed primer with Antifungal paint for top coat of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - Terrace Floor	Sqm	242.00	206.00	Rupees Two Hundred Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
122	Providing Melamine polishing of approved shade including removing and refixing of doors shutters scraping with blade and rubbing with zero size sand paper and applying sealer coat by way of spraying with necessary compressor and applying patty after rubbing with steel wool including two coats of approved shade of Melamine polish etc., complete.	Sqm	19.00	895.00	Rupees Eight Hundred Ninety Five Only
123	KSRB 15-17.5 : Applying priming coat over new wood surface and / or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications.	Sqm	71.00	51.00	Rupees Fifty One Only
124	Providing and applying painting two coats on new wood surface and/ or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foregn matter, sand papering including cost of materials, labour complete as per specifications.	Sqm	70.80	104.00	Rupees One Hundred Four Only
125	KSRB 15-18.1 : Applying Red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqm	510.80	36.00	Rupees Thirty Six Only
126	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	510.80	102.00	Rupees One Hundred Two Only
127	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - Ground Floor	Sqm	14.00	2348.00	Rupees Two Thousand Three Hundred Forty Eight Only
128	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - First Floor	Sqm	9.10	2349.00	Rupees Two Thousand Three Hundred Forty Nine Only
129	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - Second Floor	Sqm	9.10	2351.00	Rupees Two Thousand Three Hundred Fifty One Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	
130	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - Third Floor	Sqm	9.10	2353.00	Rupees Two Thousand Three Hundred Fifty Three Only
131	Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, mortar, labour, curing complete as per specifications. S	Sqm	24.50	3924.00	Rupees Three Thousand Nine Hundred Twenty Four Only
132	Flooring with 20 mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications.	Sqm	139.10	1489.00	Rupees One Thousand Four Hundred Eighty Nine Only
133	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Ground Floor	Sqm	102.30	4950.00	Rupees Four Thousand Nine Hundred Fifty Only
134	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - First Floor	Sqm	27.40	4952.00	Rupees Four Thousand Nine Hundred Fifty Two Only
135	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Second Floor	Sqm	27.40	4953.00	Rupees Four Thousand Nine Hundred Fifty Three Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
136	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Third Floor	Sqm	27.40	4955.00	Rupees Four Thousand Nine Hundred Fifty Five Only
137	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - Ground Floor	Sqm	274.30	3173.00	Rupees Three Thousand One Hundred Seventy Three Only
138	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - First	Sqm	52.50	3175.00	Rupees Three Thousand One Hundred Seventy Five Only

Scanned by CamScanner

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words
1	2	3	4	5	6
140	Providing and laying flooring for corridors/lobbies using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and preflamed 19mm thick grey granite @ 22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - _do_ using 19mm thick granite width not less than 1200mm - Third Floor	Sqm	52.50	3179.00	Rupees Three Thousand One Hundred Seventy Nine Only
141	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Ground Floor	Sqm	51.60	1390.00	Rupees One Thousand Three Hundred Ninety Only
142	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - First Floor	Sqm	492.10	1392.00	Rupees One Thousand Three Hundred Ninety Two Only
143	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Second Floor	Sqm	337.30	1394.00	Rupees One Thousand Three Hundred Ninety Four Only
144	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Third Floor	Sqm	337.30	1396.00	Rupees One Thousand Three Hundred Ninety Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
145	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete as per specification.	Sqm	102.00	4379.00	Rupees Four Thousand Three Hundred Seventy Nine Only
146	Providing full nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmtr	60.00	295.00	Rupees Two Hundred Ninety Five Only
147	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmtr	55.00	196.00	Rupees One Hundred Ninety Six Only
148	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications, size 30x30cms - Ground Floor	Sqm	16.40	1460.00	Rupees One Thousand Four Hundred Sixty Only
149	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications, size 30x30cms - First Floor	Sqm	15.30	1462.00	Rupees One Thousand Four Hundred Sixty Two Only
150	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications, size 30x30cms - Second Floor	Sqm	9.30	1464.00	Rupees One Thousand Four Hundred Sixty Four Only
151	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications, size 30x30cms - Third Floor	Sqm	9.30	1466.00	Rupees One Thousand Four Hundred Sixty Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner